

First Time Telemetry Service Reservoirs & Treated Water Storage – Solar Powered Kiosks Client: Scottish Water

Project Scope:

Provide Telemetry and Level instrumentation at 43 sites throughout Scotland that Scottish Water currently have no visibility of. This allows Scottish Water's control centre 24 hour remote visibility. This also allows operations staff the chance to view tank level trends to optimise supply and demand during peak times.

Services Provided:

- Civils and Groundworks to install new concrete plinth's and ducting.
- Installation of 31 new solar powered telemetry kiosks.
- Installation of level instrumentation into each tank to provide real-time data of each tank's contents.
- Provision of operation and maintenance manuals for each kiosk.
- To design, build & install solar powered kiosks to sites with no mains power available.

